

Vinton Trail Master Plan



Trail Issues

1. MAY REQUIRE PARKING RESTRICTIONS
2. MAY REQUIRE ARMY CORPS OF ENGINEERS REVIEW FOR FLOODPLAIN PERMIT

Trail Cost Opinion

CLEARING AND GRUBBING	\$27,000
PAVEMENT REMOVAL	\$500
GRADING FOR HARD-SURFACED TRAILS, 14' WIDE	\$45,600
GRADING FOR WALKING NATURE TRAIL	\$10,000
UTILITY ADJUSTMENTS	\$5,000
STORM SEWER/CULVERTS	\$10,000
4" GRANULAR SUBBASE	\$19,000
5" PCC TRAIL, 10' WIDE	\$106,400
ADA CURB RAMP TREATMENT	\$2,400
SEEDING/FERTILIZING/MULCHING	\$1,870
BIKE RACK/BENCHES	\$2,000
PAINTED PAVEMENT SYMBOLS	\$1,300
TRAIL SIGNAGE	\$4,000
TRAILHEAD AMENITIES	\$2,000
ESTIMATED CONSTRUCTION COST	\$237,070
25% CONTINGENCY AND ENGINEERING	\$59,300
TRAIL SEGMENT TOTAL COST	\$296,370

THESE COSTS ARE BASED ON OCTOBER 2008 DOLLARS AND SHOULD BE ADJUSTED TO THE ANTICIPATING BIDDING DATE.

Riverside Park Loop Trail Segment

